CHITALDROOG DIVISION.

ADVERTISEMENT.

The 31st May 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldroog Division, up to 30th June 1888, for constructing a Taluk Cutcherry at Holalkere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldroog between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of Work.	Unit of Work.	Rate per Unit.
Stone in chunam	C. Ft.	12,182
Brick in chunam	do	20,625
Slab stone work	do	379
Arch work	do	695
Cornice work	R. Ft.	1,128
Plastering	Sqr.	285·54
White washing	do	156·00
Color washing	do	129·00
Roofing with Mangalore tiles, teak reepers, &c., ...	do	69·64
Flat terraced roofing	do	1·56
Bengal terrace	do	13·32
Concrete flooring including plastering ..	do	42·02
Gravelling flooring	C. Yd.	8
Wood work teak	C. Ft.	5·11
Earth work foundation (excavation)	C. Yd.	5·22
Filling in basement	L. S. Rs.	20
Iron wrought	lbs.	3·73
Painting (chocolate)	Sqr.	28·74
Wood oiling	do	41·48
Bamboo matting	do	28·87
Doors to Treasury room 3′ × 6′ with iron, &c.	No.	1
Doors small 3′ × 6′ panneled	do	17
Do 3′ × 6′ battened	do	5
Do large 5′ × 6′ do	do	1
Windows large 4′ × 5′ iron bars, &c.	do	4
Do small 3′ × 4′ do	do	12
Do Venitians 1½′ × 3½′ do	do	2
Do panneled 3′ × 4′ iron bars	do	10
Do battened with iron bars 3′ × 1½′ ..	do	7
Do do 2′ × 1½′	do	9

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes as earnest money, and be superscribed "Tender for constructing a Taluk Cutcherry at Holalkere", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

D. RANGA RAO,
Offg. Executive Engineer.